

Construction Checklist

When building a new home or adding on to your current home, there are a few important things to keep in mind. The following checklist will assist you in ensuring that the appropriate factors have been considered:

- Evaluate the Site:** Before construction begins, evaluate the entire site, marking for protection of any important trees and associated rooting zones, unique areas to be preserved, streams, wetlands, potential hydric soils, and vegetation suitable for filter strips, especially in perimeter areas. Remember to call the *Ohio Utilities Protection Service (OUPS)* at 800-362-2764 48 hours before you dig, as well as the *Oil and Gas Producers Underground Protection Service* at 800-925-0988.
- Install Perimeter Controls:** Identify the areas where sediment runoff could leave the construction site and install perimeter controls to minimize the potential for off-site sedimentation. This could include leaving a buffer strip, using silt fence, and protection of storm sewer inlets.
- Build the Structures and Install Utilities:** Construct the home or addition and install utilities, as well as the sewage disposal system and well, if applicable.
- Maintenance:** Maintain all erosion and sediment control measures until construction is complete and the lot is stabilized. Inspect at least once per week and after a storm event. Sweep or scrape soil tracked onto roadways.
- Revegetate the Site:** Immediately after all outside activities are complete, stabilize the lot with seed, sod, and mulch. Redistribute the stockpiled soil, and spread to a depth of 4-6 inches over rough-graded areas. Spread mulch on newly seeded areas.
- Remove Remaining Temporary Control Measures:** Once the sod and/or vegetation is established, remove any temporary erosion and sediment control measures.

This brochure created by the Staff of the Geauga Soil and Water Conservation District under the authority of the Board of Supervisors and assistance from the USDA—Natural Resources Conservation Service.

Major funding for this brochure was made possible by a Great Lakes Commission - Great Lakes Basin Program for Soil Erosion and Sediment Control Grant and continuing financial support from the Geauga County Commissioners and ODNR—Ohio Soil and Water Conservation Commission.

Information for this brochure was taken in part from *Erosion Control for the Homebuilder* published by Summit SWCD, *Erosion and Sediment Control for Homebuilders* published by Lake SWCD, and *Rainwater and Land Development Manual*



Gauga Soil and Water Conservation District

14269 Claridon-Troy Rd.
PO Box 410
Burton, Ohio 44021

440-834-1122
Fax: 440-834-0316
gswcd@geaugaswcd.com

Gauga SWCD Mission:

"To conserve, protect, and enhance the resources of Geauga County by providing leadership, education, and assistance to all."

Last Revision: 11/30/05

All services are provided without regard to race, religion, gender, age, physical or mental handicap, national origin or politics.



Gauga Soil and Water Conservation District

Erosion and Sediment Control

A Guide for Individual Lot Construction

Gauga Soil & Water Conservation District

14269 Claridon-Troy Rd.
PO Box 410
Burton, Ohio 44021
440-834-1122
Fax: 440-834-0316
gswcd@geaugaswcd.com
website: www.geaugaswcd.com

Erosion and Sediment Control: The Key to Clean Water

Sediment is the product of erosion, and it is the largest pollutant in Ohio streams and rivers. Construction and other earth disturbing activities contribute large quantities of sediment to streams, and is carried through ditches and other conveyances throughout a watershed.

Sediment negatively impacts water quality by degrading the habitat of aquatic organisms and fish, impeding recreational opportunities, decreasing property value, and promoting the growth of weeds and algae. Sediment accumulation in ditches, streams, and lakes reduces their capacity, therefore increasing the chance of frequent flooding.

The Geauga Soil and Water Conservation District (SWCD) has the authority through the *Gauga County Water Management and Sediment Control Regulations (WMSC)* to regulate construction sites to ensure sediment remains on site. Whether or not a township requires an erosion and sediment control plan for individual lot construction, all homeowners on **any size lot are required to comply** with the provisions outlined in the WMSC Regulations. The homeowner is ultimately responsible if these measures are not properly in place.

This brochure is designed to provide Best Management Practices (BMPs) for individual lot construction to ensure that all necessary measures are taken to prevent sediment from leaving the site and entering streams and rivers. Contact the District for a complete set of regulations.



Best Management Practices for Individual Lot Construction

When Best Management Practices (BMPs) are installed and maintained correctly, they can help ensure that sediment generated from construction activity remains onsite. The following BMPs are commonly used for individual lot construction:

Construction Entrance

- Use large stone
- Install during clearing phase
- Use to prevent tracking soil onto road
- Maintain throughout construction



Sediment Barriers

- Use to filter sheet flow runoff
- Install during clearing phase
- Use combination barriers when necessary
- Make sure it is installed correctly by entrenching a portion of barrier in the ground, so it can trap sediment and intercept runoff
- Maintain until vegetation is established
- Do not use on steep slopes or concentrated flow areas



Sediment Cleanup

- At the end of each work day sweep or scrape soil tracked on to roads
- After storm events inspect for off-site sediment movement and repair damage to barriers
- Remove sediment that penetrated barriers and clean build-up



Rock Outlet Protection

- Use to dissipate energy from concentrated flows
- Helps prevent eroded channels downstream
- Use oversized stone appropriate for design velocities



Inlet Protection:

- Protect all storm sewer inlets– they are a direct conveyance to streams and rivers
- Filter fabric and temporary seeding are standard for inlet protection



Stockpile Placement and Protection

- Build stockpiles away from critical areas such as streams, drainageways, and storm sewer inlets
- Temporarily seed or mulch then immediately to protect against erosion



Re-vegetation/Surface Protection

Ground cover is the most effective way to control sediment runoff, whether it be temporary or permanent

- Use seed or sod to cover exposed soils after final grade completed
- Use temporary seed, such as annual rye, to stabilize pile until removed or re-graded
- Seed critical areas such as drainage swales, right-of-way areas, areas near curb inlets, buffer areas along streams and wetlands
- Mulching can be used when temporary seeding is not practical and can be done in any weather situation

